

From: "Semborski, Chuck" <Charles.Semborski@PacifiCorp.com>
To: "Thomas W Lloyd" <twlloyd@fs.fed.us>, "Pam Grubaugh-Littig" <pamgrubaughlittig@utah.gov>
Date: 5/9/2005 1:51:58 PM
Subject: Revised Mill Fork Coal Exploration Plan Email #1

Energy West Mining Company
2005 Coal Exploration Program (originals sent by mail):
<<Coal Ownership Revised Plan.pdf>> <<Surface Ownership Revised Plan.pdf>> <<Upper Joes Valley Photo #2.pdf>> <<Upper Joes Valley Photo #1.pdf>> <<Drilling Plan Revised April 2005.pdf>> <<DOGM Cover Revised Plan.pdf>>
As outlined in the plan, PacifiCorp proposes to revise the exploration plan to reduce the total number of exploration holes from six (6) to four (4). Of the four proposed locations, three are revised, the fourth remained as proposed in March 2005. The March submittal proposed drilling a total of six (6) holes, with five of the six located in the southwestern portion of the Mill Fork State Lease ML-48258. Recently, development mining in the Mill Fork Lease intercepted a complex series of rock splits which requires revising the exploration plan to assist in the interpretation of the geology. PacifiCorp proposes to delete five locations in the extreme southwestern portion of the lease and proposes relocating three sites north of these original locations.

All of the exploration will utilize helicopter supported technics. To minimize potential impacts to wildlife including raptors, PacifiCorp proposes to commence drilling on July 15, 2005.

If you have questions please call.

Chuck Semborski
Manager of Geology/Permitting
Energy West Mining Company
P.O. Box 310
Huntington, Utah 84528
Phone:
Work - (435)687-4720
Cell - (435)650-5355

This email is confidential and may be legally privileged.

It is intended solely for the addressee. Access to this email by anyone else, unless expressly approved by the sender or an authorized addressee, is unauthorized.

If you are not the intended recipient, any disclosure, copying, distribution or any action omitted or taken in reliance on it, is prohibited and may be unlawful. If you believe that you have received this email in error, please contact the sender, delete this e-mail and destroy all copies.

=====

CC: <stevedemczak@utah.gov>



May 3, 2005

Utah Coal Regulatory Program
Division of Oil, Gas and Mining
1594 North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

**RE: NOTICE OF INTENTION TO CONDUCT MINOR COAL EXPLORATION -
UTAH STATE COAL LEASE ML-48258 - REVISED PLAN; PACIFICORP,
ENERGY WEST MINING CO., EMERY COUNTY, UTAH**

PacifiCorp, by and through its wholly-owned subsidiary, Energy West Mining Company ("Energy West") as mine operator, hereby submits two (2) copies of the Notice of Intention to Conduct Minor Coal Exploration - Utah State Coal Lease ML-48258 - Revised Plan. One copy of the application has been sent directly to the Price Field Office.

On March 3, 2005 Energy West submitted an application to conduct a minor coal surface exploration drilling program during the 2005 field season. As outlined in the proposal, a total of six drill holes were planned within the current Utah State Coal Lease ML-48258, in Sections 11, 22, and 23, Township 16 South, Range 6 East, Salt Lake Base and Meridian. Recently, development mining in the Mill Fork Lease intercepted a complex series of rock splits which requires revising the exploration plan to assist in the interpretation of the geology. PacifiCorp proposes to revise the exploration plan to reduce the total number of exploration holes from six to four. Of the four proposed locations, three are revised, the fourth remained as proposed in March 2005. The drilling will occur on lands in which the surface is administered by the U.S.D.A. Forest Service (USFS) and the subsurface by the State of Utah (see accompanying drilling application maps entitled Mill Fork Coal Lease - Coal Exploration - General Location Maps, Aerial Photos, Surface Ownership Map, Coal Ownership Map, Waterline and Pump Location Map).

The proposed holes will be drilled in un-named drainages which report to Indian Creek, all in Emery County, Utah. The staging area for these holes will be in Upper Joes Valley or in the lower end of Mill Fork Canyon (see Raptor Locations, Helicopter Flight Paths and Staging Areas map).

May 3, 2005

Division of Oil, Gas and Mining

Notice of Intention to Conduct Minor Coal Exploration - Revised Plan

Page Two

Energy West has strategically selected the proposed drill hole locations to minimize environmental impacts and to maximize geologic data. As outlined in the Notice of Intention, no site preparation (building roads or drill pads) will be necessary. To minimize potential impacts to wildlife including raptors, PacifiCorp proposes to commence helicopter supported drilling operations on July 15, 2005. Energy West goes to great extents to minimize environmental impacts, including selecting minimal impact drilling techniques, selecting easily reclaimable sites, protecting existing vegetation with a protective cover, selecting drill equipment that can be leveled without excavating the ground, and complete cleanup and reclamation of drill sites.

If you require any additional information please call me at (435) 687-4720.

Thank you for your assistance in this matter.

Sincerely,

Charles A. Semborski

Charles A. Semborski

Geology/Permitting Supervisor

Enclosures (2 copies)

cc: Steve Demczak, (DOGM-Price Office) w/encl.
U.S.F.S. Alice Carlton, Forest Supervisor w/encl. (3)
Mesia Nyman, District Ranger
Tom Lloyd, Geologist w/encl.
Chris Colt, (DWR) w/encl.
Don Stephens (BLM) w/encl.
File

**NOTICE OF INTENTION TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

REVISED APRIL 2005

C/O Interstate Mining Company
(Managing Agent)



Energy West Mining Company
(Mine Operator)



**NOTICE OF INTENTION TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

APRIL 2005

TABLE OF CONTENTS

R645-200. Coal Exploration: Introduction.	1
R645-200-100. Scope. (Minor Coal Exploration):	1
122. Minor Coal Exploration.	1
R-645-200-200. Responsibilities.	1
210. Responsibility to Comply with Regulations.	1
220. Responsibility of the Division to Review and Reply.	1
230. Responsibility of the Division to Coordinate with Other Agencies.	1
R645-201. Coal Exploration: Requirements for Exploration Approval.	1
R645-201-100. Responsibilities for Coal Exploration Plan Review.	1
110. Coal Exploration Plan Review, Responsibility of Division.	1
120. Requirements of 48 CFR 3480-3487.	2
130. Division Responsibility to Coordinate with Other Agencies.	2
R645-201-200. Notices of Intention to Conduct Minor Coal Exploration.	2
210. Division Review Requirement.	2
220. Required Applicant Information.	2
221. Name, Address, and Telephone Number of Applicant.	2
222. Name, Address, and Telephone Number of the Applicant's Representatives.	3
223. Description of Exploration Area.	3
224. Period of Intended Exploration.	4
225. Method of Exploration.	4
R645-202. Coal Exploration: Compliance Duties.	8
R645-202-100. Required Documents.	8
Road Use Permits:	8
Special Use Permit:	8
Archeological Information:	8
R645-202-200. Performance Standards.	9
210. Requirements of the State Program.	9
220. Inspection and Enforcement.	9
230. Operational Standards.	10
231. Non-Disturbance of Habitats.	10
232. Road Construction and Use.	12
233. Topsoil Removal and Storage.	12
234. Diversions of Overland Flows.	12
235. Minimizing Disturbance to Hydrologic Balance.	13
236. Acid- or Toxic Forming Materials.	13
240. Reclamation Standards.	13
241. Excavations.	13
242. Re-Vegetation.	13
242.1 Re-Seeding.	13
242.2 Soil Surface Stability.	14
243. Reclamation of Boreholes.	15
244. Removal of Equipment.	15
R645-203. Coal Exploration: Public Availability of Information.	16
R645-203-100. Public Records.	16

LIST OF MAPS

2005 COAL EXPLORATION - GENERAL LOCATION (1"=3000')
2005 COAL EXPLORATION - AERIAL PHOTOS (Upper Joes Valley - 2 Photos)
2005 COAL EXPLORATION - SURFACE OWNERSHIP MAP
2005 COAL EXPLORATION - COAL OWNERSHIP MAP
2005 COAL EXPLORATION - RAPTOR LOCATIONS, FLIGHT PATHS AND STAGING AREAS MAP
2005 COAL EXPLORATION - WATERLINE AND PUMP LOCATION MAP

**NOTICE OF INTENT TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

R645-200. Coal Exploration: Introduction.

PacifiCorp originally submitted an exploration plan in March 2005 to drill a total of six (6) exploration holes within the Mill Fork Coal Lease ML-48258 in the year 2005. Recently development mining in the Mill Fork Lease intercepted a complex series of rock splits which requires revising the exploration plan to assist in the interpretation of the geology. PacifiCorp proposes to revise the exploration plan to reduce the total number of exploration holes from six (6) to four (4). Of the four proposed locations, three are revised, the fourth remained as proposed in March 2005. For ease of reference, this plan follows the format of the applicable portions of the Utah Division of Oil, Gas, and Mining (hereinafter referred to as "the Division") rules (R645-200 through R645-203) regarding Coal Exploration.

R645-200-100. Scope. (Minor Coal Exploration):

- 122. Minor Coal Exploration.** PacifiCorp intends to drill four (4) 3" diameter core holes that will intercept 1 or more coal seams each. The exploration will occur on a designated Utah state coal lease (ML-48258). Less than 250 tons of coal will be removed. PacifiCorp is hereby filing a Notice of Intention to Conduct Minor Coal Exploration under the requirements of R645-201-200.

R-645-200-200. Responsibilities.

- 210. Responsibility to Comply with Regulations.** PacifiCorp will comply with the requirements of R645-200 through R645-303.
- 220. Responsibility of the Division to Review and Reply.** The Division will receive and review this Notice of Intention to Conduct Minor Coal Exploration. The Division will review and reply within 15 days.
- 230. Responsibility of the Division to Coordinate with Other Agencies.** The Division will coordinate review of this Notice with the other appropriate government agencies (SITLA, U.S.D.A. Forest Service, BLM, OSM, etc.). PacifiCorp will provide enough copies of this notice to the Division for distribution to these agencies.

R645-201. Coal Exploration: Requirements for Exploration Approval.

R645-201-100. Responsibilities for Coal Exploration Plan Review.

- 110. Coal Exploration Plan Review, Responsibility of Division.** The lands on which this exploration will be conducted, being a state coal lease issued to PacifiCorp, are not subject

**NOTICE OF INTENT TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

to 43 CFR Parts 3480-3487. Therefore, exploration plan review will be the responsibility of the Division.

- 120. Requirements of 43 CFR 3480-3487.** N.A.
- 130. Division Responsibility to Coordinate with Other Agencies.** This Notice of Intention to Conduct Minor Coal Exploration and Drilling Plan will be submitted to the Division as the lead agency for review and approval.

R645-201-200. Notices of Intention to Conduct Minor Coal Exploration.

- 210. Division Review Requirement.** Notices of Intention to Conduct Minor Coal Exploration where 250 tons or less of coal will be removed require Division review prior to conducting exploration. PacifiCorp originally submitted the Notice to the Division in March of 2005, allowing the Division and other agencies time to review and approve the Notice before exploration activities begin on June 15, 2005. The March submittal proposed drilling a total of six (6) holes, with five of the six located in the southwestern portion of the Mill Fork State Lease ML-48258. Recently development mining in the Mill Fork Lease intercepted a complex series of rock splits which requires revising the exploration plan to assist in the interpretation of the geology. PacifiCorp proposes to delete five locations in the extreme southwestern portion of the lease and proposes relocating three sites north of these original locations.
- 220. Required Applicant Information.** This Notice of Intention to Conduct Minor Coal Exploration is required to include the following pertinent information.

221. Name, Address, and Telephone Number of Applicant:

APPLICANT:

PacifiCorp
One Utah Center
201 South Main, Suite 2100
Salt Lake City, Utah 84140-0021
(801)220-4612

**NOTICE OF INTENT TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

OPERATOR:

Energy West Mining Company
15 North Main Street
Huntington, Utah 84528
(801)687-9821

222. Name, Address, and Telephone Number of the Applicant's Representatives:

RESPONSIBLE REPRESENTATIVE:

Chuck Semborski or Ken Fleck
Energy West Mining Company
15 North Main Street
P.O. Box 301
Huntington, Utah 84528
(435)687-4720
(435)687-6638

223. Description of Exploration Area. Narrative and map describing the exploration area and indicating where exploration will occur:

PROPOSED EXPLORATION AREA:

The proposed drill holes are located within the current Utah State Coal Lease ML-48258, in Sections 11, 14 and 22, Township 16 South, Range 6 East, Salt Lake Base and Meridian. The drilling will occur on lands in which the surface is administered by the U.S.D.A. Forest Service (USFS) and the subsurface by the State of Utah (see accompanying maps entitled Mill Fork Coal Lease - Coal Exploration - General Location Maps, Aerial Photos, Surface Ownership Map, Coal Ownership Map).

The proposed holes will be drilled in Upper Joes Valley, site 2005-1, 2005-2, and 2005-3 south of the Indian Creek campground and site 2005-4 north of the Indian Creek campground.

**NOTICE OF INTENT TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

All four sites will be located above the Castlegate Sandstone. Access to this location will be from Upper Joes Valley and/or Mill Fork. The staging area for this hole will be in Upper Joes Valley or in the lower end of Mill Fork Canyon (see Raptor Locations, Helicopter Flight Paths and Staging Areas map).

Table 1. Mill Fork Coal Lease Proposed Drilling for 2005 (Revised April 2005):

HOLE NUMBER	LOCATION	ELEVATION (Feet)	DEPTH (Ft)	SURFACE OWNERSHIP	COAL OWNERSHIP
2005-1	1960' West, 860' South of the NE Corner of Sec. 22, T. 16S., R. 6E.	9450'	1500'	USFS	State Coal Lease ML-48258
2005-2	2170' West, 0' South of the NE Corner of Sec. 22, T. 16S., R. 6E.	9510'	1600'	USFS	State Coal Lease ML-48258
2005-3	210' East, 890' North of the SW Corner of Sec. 14, T. 16S., R. 6E.	9450'	1500'	USFS	State Coal Lease ML-48258
2005-4	725' South, 320' East of the NW Corner of Sec. 11, T. 16S., R. 6E.	9610'	1600'	USFS	State Coal Lease ML-48258

224. Period of Intended Exploration:

PROJECT STARTUP DATE:

Helicopter Supported Drill Holes 2005 1-4 July 15, 2005

PROJECT COMPLETION DATE:

August 15, 2005

It is anticipated that all drilling and reclamation activities associated with this project will be completed within 60 days following the date of implementation.

225. Method of Exploration. Method of exploration to be used, amount of coal to be removed, and practices to be used to protect the area from adverse impacts and reclaim the area in accordance with R645-202:

The method of exploration to be used is helicopter-assisted drilling, in which the primary mode of transportation for drilling equipment and personnel is by

**NOTICE OF INTENT TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

helicopter, rather than by road. By using this method, drilling equipment can be transported into remote areas inaccessible by road to conventional drilling rigs, and environmental impact to the surface is minimized. All drills, drilling equipment, and personnel will be transported to the individual drilling sites by helicopter from staging areas located on existing roads (see Raptor Locations, Flight Paths and Staging Areas Map).

Pre-Work Meeting:

A pre-work meeting including the responsible company representatives, contractors, State of Utah Institutional Trust Lands Administration, and the Forest Service will be conducted at the project location prior to commencement of operations.

Drill Methods & Procedures: Three inch maximum diameter holes will be core or rotary drilled the entire length to the approximate depths stated previously in the drill hole location and depth table. Drilling depth will be sufficient to accomplish penetration through both the Blind Canyon and Hiawatha coal seams, and to enter the Star Point Sandstone. The drilling will be done by a drilling contractor(s) experienced in helicopter supported drilling. The drills used are diesel powered rotary drill rigs mounted on 6' x 8' skids. Drilling will utilize water and, as necessary, a biodegradable polymer drilling "mud" such as MINEX 1330 (MSDS available upon request).

The following support equipment will be required:

- 3 pickup trucks: stationed at the staging area
- 1 Flatbed semi-trailer for mobilization/de-mobilization of the drill rig
- 1 Lama helicopter and support truck
- 1 Storage trailer to be stationed at the staging area

The drill rig components and associated materials, tools and equipment will be transported by truck to the helicopter staging areas indicated on the accompanying map. The tools and materials and personnel necessary for site preparation will be transported to the drill site by helicopter. Site preparation will include removal of dead-fall and brush as necessary. Minor digging, using hand tools, may be necessary at some locations to achieve effective placement of the leveling support materials (wood blocks, etc.). Brattice or other similar material will be placed on the ground beneath the drill rig. The drill rig is made up of several components

**NOTICE OF INTENT TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

which will be transported to the site by helicopter in several "lifts". The drill rig components will then be assembled at the drill site, the rig will be leveled and other necessary materials will be flown to the site.

Drill Hole Access and Pad Construction:

No access road or pad construction will be necessary for the proposed project. Drilling equipment and materials will be transported to the drill site by helicopter. Personnel will access the site by vehicle and helicopter via existing roads and on foot. The drill sites are relatively level (20 percent or less slope); therefore, minimal site preparation will be necessary. Vegetation, in the form of trees, grasses, forbs and sparse, low shrubs, will not be removed. However, it may be necessary to remove dead-fall and some "taller" shrubs (mahogany, etc.)/aspen trees for safety reasons. This will be minimized and accomplished using hand tools. The dead-fall will be replaced upon completion of drilling. An area no larger than approximately 40' by 40' will be occupied at the drill site. Leveling of drilling equipment will be accomplished using hand tools and supports (wood blocks, etc.) transported to the site by helicopter. All materials, tools and equipment will be removed immediately upon completion of drilling and reclamation activities.

A 1" diameter high-pressure hose will be laid overland from the pump stations to each drill site. This will be accomplished by hand and/or helicopter. No clearing of vegetation will be necessary for placement of the water hose. Existing openings among the trees will be utilized for water line placement. No vegetation clearing will occur at the water tank/pump sites or the helicopter staging areas. Activities will be confined to the existing roads in Cottonwood Canyon, Mill Fork Canyon and Indian Creek. The necessary approvals will be obtained from the U.S. Forest Service for activities associated with the respective roads.

Amount of Coal to be Removed: As previously discussed, a 3" maximum diameter hole will be core or rotary drilled for the entire depth of the hole. The hole will penetrate through both the Blind Canyon and Hiawatha coal seams. The core and/or cuttings will be examined to determine coal seam characteristics. This will result in approximately a maximum of 20 pounds of coal being removed per hole, with a total of about 120 pounds removed for study and analysis.

Practices to Protect from Adverse Impacts and to Reclaim the Area: During drilling, water and drilling fluids will be recirculated to the extent possible. Any returned cuttings and other materials will be captured in a container at the drill

**NOTICE OF INTENT TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

site. The cuttings will be transported from the drill site to the staging area by helicopter and then by vehicle to the Deer Creek or Cottonwood Waste Rock sites for disposal. Containment of possible fluid spills will be achieved through the use of brattice ground cover, silt fence, and if necessary, earthen berms. If spills occur, all affected materials will be removed from the site and disposed of at an approved location. If soil is removed during spill containment and clean-up, the site of removal will be recontoured and seeded with the approved seed mixture.

In order to minimize impacts to wildlife, particularly raptors, all non-essential helicopter flight paths will be 1,000 feet above terrain whenever possible between landing zones or drill sites.

Fire Suppression Equipment:

All gasoline and diesel powered equipment will be equipped with effective mufflers or spark arresters which meet applicable Forest Service specifications. Fire suppression equipment will be available to all personnel working at the project site. Equipment will include at least one hand tool per crew member consisting of shovels and pulaskis and one properly rated fire extinguisher per vehicle and/or combustion engine.

Fuel and/or lubricating oil containers not stored in a truck will be placed on brattice or other acceptable ground cover at a site located away from drainage channels and surrounded by brattice, earthen berm or other acceptable containment structure. If spills occur, clean-up will be conducted as stated above.

Access by personnel associated with the drilling project will be via vehicle or helicopter to Mill Fork Canyon and Indian Creek and by foot to the drill site. Therefore, no additional access facilities will be constructed.

Following completion of drilling and cementing of the hole, the drill rig and all associated equipment and materials will be removed by helicopter to the helicopter staging areas and transported from the area by vehicle. The water hose, tanks and pumping station and all associated materials and equipment will be removed. All trash and extraneous materials will be removed from the US Forest Service property and disposed of at an approved location. The sites will be reclaimed by: 1) Removing all trash, cuttings, and contaminated soil. 2) Recontouring site to original contour, and 3) Re-seeding with the approved seed mix, and scattering deadfall over the site.

**NOTICE OF INTENT TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

**R645-202. Coal Exploration: Compliance Duties.
R645-202-100. Required Documents.**

“Each person who conducts coal exploration which substantially disturbs the natural land surface will, while in the exploration area, have available a copy of the Notice of Intention to Conduct Minor Coal Exploration...for review by an authorized representative of the Division upon request.”

Road Use Permits:

The Forest Service will be notified 48 hours in advance that heavy equipment will be moved onto National Forest System lands and that surface disturbing activities will commence.

Mill Fork Canyon (U.S. Forest Development Road #245): Prior to drilling, Energy West will obtain a permit from the U.S. Forest Service for the helicopter staging area located along U.S. Forest Service Road #245 in Section 21, Township 16 South, Range 7 East.

Cottonwood Creek (U.S. Forest Development Road #040): Prior to drilling, Energy West will obtain a permit from the U.S. Forest Service for the helicopter staging area at the head of Cottonwood Canyon (Flat Canyon), and for use of U.S. Forest Service Road #040 in Sections 22, 27, 35, Township 16 South, Range 6 East and Sections 2, 3, 10, 11, 14, 23, 24 and 25, Township 17 South, Range 6 East.

Indian Creek (U.S. Forest Development Road #017): Prior to drilling, Energy West will obtain a permit from the U.S. Forest Service for the helicopter staging area located along the east side of U.S. Forest Service Road #221 in Section 15, Township 16 South, Range 6 East.

Special Use Permit:

As required by the U.S. Forest Service, PacifiCorp will apply for a Special-Use Application (Form 2700-3) for the proposed exploration. Each drill site will occupy approximately 0.04 acre for a total area of use of approximately 0.16 acres.

Archeological Information:

The proposed locations in Upper Joes Valley, are located on the western flank of East Mountain above Indian Creek. As detailed in the previous section, no earthwork or excavation is necessary utilizing helicopter supported drilling techniques.

**NOTICE OF INTENT TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

As required by the U.S.D.A. Forest Service for the 2004 drilling program, PacifiCorp contracted SENCO-PHENIX Archeological Services (Price, Utah) to conduct a file search and field survey for the proposed drilling activities. After the archeological field survey for the 2001 drilling program, SENCO-PHENIX recommended that PacifiCorp ask the U.S.D.A. Forest Service to waive the requirement for a field inspection of all drill sites due to the remoteness, small size, and minimal impact of the sites examined, and the limited probability of any future drill sites in the area impacting archeological resources.

For the above referenced reasons, PacifiCorp hereby requests that the requirement for a field archeological survey of each drill site be waived for the 2005 proposed drilling program.

In the unlikely event that cultural or paleontological resources are discovered during operations, all operations which may result in disturbance to the resources will cease and the Forest Service will be notified as soon as possible of the discovery.

PacifiCorp will make sufficient copies of all coal exploration permit documents, including the Notice of Intent, the Forest Service drilling stipulations, and all applicable road use, special use, and other permit documents at each drill site, and in each field vehicle used during the exploration program, for the duration of the program.

R645-202-200. Performance Standards.

- 210. Requirements of the State Program.** All coal exploration and reclamation operations which substantially disturb the natural land surface...will be conducted in accordance with the coal exploration requirements of the State Program, and any conditions on approval for exploration and reclamation imposed by the Division.

PacifiCorp will comply with all coal exploration requirements of the State Program, and any conditions on approval of the exploration plan.

- 220. Inspection and Enforcement.** Any person who conducts any coal exploration in violation of the State Program will be subject to the provisions of 40-10-20 of the Act and the applicable inspection and enforcement provisions of the R645 Rules.

PacifiCorp will comply with all coal exploration requirements of the State Program, and any conditions on approval of the exploration plan. PacifiCorp welcomes inspection of its exploration operations at any time during exploration.

**NOTICE OF INTENT TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

230. Operational Standards.

- 231. Non-Disturbance of Habitats.** Habitats of unique or unusually high value for fish, wildlife, and other related environmental values and critical habitats of endangered or threatened species identified pursuant to the Endangered Species Act of 1973 (16 U.S.C. 1531 et. seq.) will not be disturbed during coal exploration.

The vegetation in the area consists of a Cottonwood/Aspen /Fir/Dog wood community in the bottom of the canyons and Spruce-Fir Coniferous Forest inter-mixed with aspen communities on the south side slopes and dense Spruce-Fir Coniferous Forest on the north slopes. The primary land uses associated with the area are wildlife habitat, livestock grazing and recreation. The area is presently classified for the following wildlife uses by the Utah Division of Wildlife Resources (DWR):

Mule Deer	High Priority Summer Range
Elk	Critical Winter Range and High Priority Summer Range

The proposed drilling is not expected to have a detrimental impact on any of these species, their habitat or other land uses associated with the area.

Surveys for Threatened, Endangered and Sensitive (TES) plant and animal species have been conducted in connection with various projects in this area of Rilda Canyon (Surface Facilities, Permit Extension and Powerline) and the Mill Fork coal leasing process. Results of these surveys have been provided to the various regulatory agencies in the applications for the projects. No TES plants and animals have been found in the area of the proposed drill holes.

Energy West in corporation with the Division of Wildlife Resources, conducts annual raptor surveys in and adjacent to permit boundaries, including the Mill Fork State Lease ML-48258. The following table lists the nest located, specie and potential conflicts based upon the 2004 raptor survey completed with DWR (May 19, 2004):

**NOTICE OF INTENT TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

MILL FORK AREA Raptor Locations and Status - 2004 Survey Data				
Nest #	Location	Species	Status	Potential Conflict
1207	Mill Fork	Red Tail Hawk	Not Surveyed	* All Helicopter supported drilling will occur starting July 15 th * Mill Fork staging area outside ½ mile buffer * Not in direct line of sight
80	Mill Fork	Golden Eagle	Inactive	* All Helicopter supported drilling will occur starting July 15 th * Mill Fork staging area outside ½ mile buffer * Not in direct line of sight
81	Mill Fork	Golden Eagle	Inactive	* All Helicopter supported drilling will occur starting July 15 th * Mill Fork staging area outside ½ mile buffer * Not in direct line of sight
79	Mill Fork	Golden Eagle	Inactive	* All Helicopter supported drilling will occur starting July 15 th * Mill Fork staging area outside ½ mile buffer * Not in direct line of sight
963	Mill Fork	Golden Eagle	Tended	* All Helicopter supported drilling will occur starting July 15 th * Mill Fork staging area outside ½ mile buffer * Not in direct line of sight
78	Mill Fork	Golden Eagle	Inactive	* All Helicopter supported drilling will occur starting July 15 th * Mill Fork staging area outside ½ mile buffer
1210	Crandall Canyon	Golden Eagle	Inactive	None
1211	Crandall Canyon	Golden Eagle	Tended	None
1282	Crandall Canyon	Raven	Active	None
1208	Little Bear	Red Tail Hawk	Inactive	None
1283	Little Bear	Red Tail Hawk	Inactive	None
1284	Little Bear	Red Tail Hawk	Inactive	None
1285	Little Bear	Red Tail Hawk	Inactive	None
1206	Rilda Canyon	Red Tail Hawk	Inactive	None

Raptor activity in Mill Fork Area will be evaluated during the 2005 survey scheduled for May 16, 2005. PacifiCorp proposes to commence helicopter supported drilling operations on July 15, 2005. To further reduce potential raptor impacts, all non-essential flights will be conducted at 1000 feet above ground

**NOTICE OF INTENT TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

level. All proposed drill sites are outside the ½ mile buffer zones of known nest. The secondary staging area located in Mill Fork is near nests 80 and 81. As stated previously, all helicopter drilling activities will be initiated on July 15, 2005.

- 232. Road Construction and Use.** All roads or other transportation facilities used for coal exploration will comply with the applicable provisions of R645-301-358...R645-301-762.

Pacificorp will use only existing roads for this project. No new roads will be constructed.

- 233. Topsoil Removal and Storage.** Topsoil will be separately removed, stored, and redistributed on areas disturbed by coal exploration activities as necessary to assure successful revegetation or as required by the Division.

The method of drilling used by Pacificorp for these holes assures that topsoil is not disturbed except where small excavations are made necessary for leveling the rig and associated components. Brattice ground cover is used under the rig to protect the topsoil and surface vegetation; therefore the topsoil is not disturbed.

- 234. Diversions of Overland Flows.** Diversions of overland flows and ephemeral, perennial, or intermittent streams will be made in accordance with R-645-301-742.3.

Pacificorp will obtain the necessary permissions and water rights actions to take water for drilling from local drainages in the vicinity of the proposed drill holes. Water for the drill holes will be pumped/gravity fed directly from the un-named drainages located near the drill holes or from a pump located near Indian Creek itself. A gasoline/diesel powered water pump will be stationed near the creek/canal and water will be pumped to water tanks located at each drill site. No disturbance is made to the stream course.

The amount of water required for the project is estimated at 40,000 gallons per hole. Therefore, the maximum total quantity of water to be used is estimated at approximately 160,000 gallons (0.49 acre feet). A *Temporary Exchange Application* will be filed and approved with the State of Utah, Division of Water Rights prior to commencement of operations.

**NOTICE OF INTENT TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

- 235. Minimizing Disturbance to Hydrologic Balance.** Coal exploration will be conducted in a manner which minimizes disturbance to the prevailing hydrologic balance in accordance with R645-301-356.300...and R645-301-763. The Division may specify additional measures which will be adopted by any person engaged in coal exploration.

During exploration, surface disturbance will consist only that which is necessary to level the rig and associated structures. No drill pad will be constructed, so there will be no additional runoff during precipitation events. No impoundments to contain runoff will be necessary. Overall impact on the hydrologic balance will be minimal, if any.

- 236. Acid- or Toxic Forming Materials.** Acid- or toxic-forming materials will be handled and disposed of in accordance with R645-301-731.110, 731.300, and 553.260.

No Acid- or Toxic earth materials or coal waste will be produced used, or handled during this drilling program.

- 240. Reclamation Standards.**

- 241. Excavations.** If excavations, artificially flat areas, or embankments are created during exploration, these areas will be returned to the approximate original contour promptly after such features are needed for coal exploration.

The only excavations that will be made will be small shovel cuts made for leveling the rig and associated equipment. These will be promptly filled in to original contour as soon as the drilling equipment is removed from each site.

- 242. Re-Vegetation.** All Areas disturbed by coal exploration activities will be revegetated in a manner that encourages prompt revegetation and recovery of a diverse, effective, and permanent vegetative cover. Revegetation will be accomplished in accordance with the following :

- 242.1 Re-Seeding .** All areas disturbed by coal exploration activities will be seeded or planted to the same seasonal variety native to the areas disturbed. If the land use of the exploration area is intensive

**NOTICE OF INTENT TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

agriculture, planting of the crops normally grown will meet the requirements of R645-202-242.100.

All drilling areas will be promptly re-seeded upon completion of each hole, removal of equipment, and recontouring of the site, if necessary, with a seed mix approved by the surface management agency and the Division.

The following is the seed mix specified from previous years approved drilling permits, and will be used unless changes are indicated by the agencies.

<u>Species</u>	<u>lbs/acre (PLS)</u>
Basic Mix	
Columbia needle grass - <i>Stipa columbiana</i>	4.5
Slender wheatgrass - <i>Elymus trachycaulus</i>	4.5
Sandbergs bluegrass - <i>Poa secunda</i>	0.75
Pacific aster - <i>Aster chilensis</i>	0.2
Supplement*	
Sulfur flower - <i>Eriogonun umbellatum</i>	2.0
Rocky Mountain penstemon - <i>Penstemon strictus</i>	0.75

* Seed should be purchased in individual seed packets, not as mixture.

The seed mixture will be hand broadcast and the area will be hand raked following seeding to cover the seed. Following seeding, any dead-fall that was removed from the drill site will be replaced.

242.2 Soil Surface Stability. The vegetative cover will be capable of stabilizing the soil surface from erosion.

Since the soil and vegetative cover will not be removed, and the vegetation will spring back up as soon as the drilling equipment is removed, this requirement will be met.

No crops are raised in the project area. Crop replacement will not be necessary.

**NOTICE OF INTENT TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

- 243. Reclamation of Boreholes.** Each exploration hole, borehole, well, or other exposed opening created during exploration will be reclaimed in accordance with R645-301-529, R645-301-551, R645-301-631, R645-301-738, and R645-301-765.

No mine openings or exploration openings will be created, therefore R645-301-529 and R645-301-551 do not apply in this case. None of these holes will be turned into water monitoring wells, due to the lack of measurable groundwater in the area and the remote locations of the holes. Therefore, R645-301-738 and R645-301-765 do not apply.

Groundwater is not anticipated to be encountered; therefore, the proposed holes will not be retained as water monitoring wells. However, if groundwater is present, it will be reported to the appropriate agencies (SITLA, USFS, DOGM) and a determination will be made regarding the transfer and possible modification of the drill hole to a monitoring well.

Upon completion of down-hole procedures, each drill hole will be completely sealed with cement/bentonite from the bottom of the hole to ground level. The cement slurry mixture used to plug and seal the hole will be mixed in compliance with standard cement mixing tables (e.g. Halliburton). Enough cement will be mixed and pumped into the hole to completely seal the coal horizon. The remainder of the hole will be filled with a bentonite slurry to within 5' of the surface and a cement surface plug will fill the top 5'. A brass monument marker will be placed in the top of the cement surface plug with the hole number and year. The Bureau of Land Management Price Field Office will be contacted prior to completion to verify the abandonment procedures. Any variance from this procedure will be approved in advance by SITLA and DOGM.

- 244. Removal of Equipment.** All facilities and equipment will be promptly removed from the exploration area when they are no longer needed for exploration, except for those facilities and equipment that the Division determines may remain to:

244.1 Provide additional environmental data;

**NOTICE OF INTENT TO CONDUCT
MINOR COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258**

244.2 Reduce or control the on-site and off-site effects of the exploration activities;


244.3 Facilitate future coal mining and reclamation operations by the person conducting the exploration.


When each drill rig setup is no longer needed for the project, the complete assemblage of equipment will be removed immediately from the area to facilitate reclamation work and free this equipment for use elsewhere by the contractor.


Pacificorp does not anticipate needing this equipment for any further use in the exploration area.

**R645-203. Coal Exploration: Public Availability of Information.
R645-203-100. Public Records.**

Except as provided in R645-203-200, all information submitted to the Division under R645-200 will be made available for public inspection and copying at the Division.







CAD FILE NAME/DISK#: WF-2005-DRILLING-BASE-MAP.DWG

ENERGY WEST
MINING COMPANY
HUNTINGTON, UTAH 84528

2005 COAL EXPLORATION
UTAH STATE COAL LEASE ML-48258
SURFACE OWNERSHIP MAP

DRAWN BY:	K. LARSEN	DRAWING #:
SCALE:	1"=3000'	SHEET	1 OF 1
DATE:	MAY 3, 2005	REV.	...

Proposed 2005 Drilling Plan

UTAH

U.S. NATIONAL FOREST

- EXISTING HOLE
- PROPOSED HOLES

Modified from
Rilda Quadrangle
7.5 Minute Series

